ROADWAY DESIGN UTILITIES · SS-3 / SS-4

Storm sewer inlet quantities

Project: SYNTHETIC SS-3 QA

County: Test county

Prepared by: Not entered

Report date: 2026-11-01

Project quantity schedule

Inlet / station	Type	Pipe	Height (ft)	Concrete (yd³)	Steel (lb)	Grate (lb)	Frame (lb)
1 100+00	SS-3	18 in. round	3.5	0.869	76.000	200.000	244.000
2 101+00	SS-4	15 in. round	4.5	0.894	31.000	—	—
3 102+00	SS-3	18 in. round	3.5	0.869	76.000	200.000	244.000
4 103+00	SS-4	15 in. round	4.5	0.894	31.000	—	—
5 104+00	SS-3	18 in. round	3.5	0.869	76.000	200.000	244.000
6 105+00	SS-4	15 in. round	4.5	0.894	31.000	—	—
7 106+00	SS-3	18 in. round	3.5	0.869	76.000	200.000	244.000
8 107+00	SS-4	15 in. round	4.5	0.894	31.000	—	—
9 108+00	SS-3	18 in. round	3.5	0.869	76.000	200.000	244.000
10 109+00	SS-4	15 in. round	4.5	0.894	31.000	—	—
11 110+00	SS-3	18 in. round	3.5	0.869	76.000	200.000	244.000
12 111+00	SS-4	15 in. round	4.5	0.894	31.000	—	—
Project total · 12 inlets				**10.580**	**642.000**	**1,200.000**	**1,464.000**

One pipe-opening deduction per inlet is included. SS-4 grate and frame weights are not reported; project grate/frame totals include SS-3 inlets only. Totals use unrounded inlet quantities; displayed values are rounded to three decimals.

Inlet calculation details

Inlet 1 · SS-3

Station: 100+00
Pipe: 18 in. round
Entered height: 3.5 ft
Listed minimum: 3.5 ft
Grate: 200.000 lb
Frame: 244.000 lb

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.5 ft)	0.869	76.000
Additional height (0.0000 ft)	0.000	0.000
Inlet quantity	0.869	76.000

Additional height uses 0.184 yd³/ft of concrete and 17 lb/ft of reinforcement. Grate and frame weights are fixed at 200 lb and 244 lb per SS-3 inlet.

Inlet 2 · SS-4

Station: 101+00
Pipe: 15 in. round
Entered height: 4.5 ft
Listed minimum: 3.125 ft
Grate: —
Frame: —

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.125 ft)	0.640	31.000
Additional height (1.3750 ft)	0.254	0.000
Inlet quantity	0.894	31.000

Additional height increases concrete by 0.185 yd³/ft only. Reinforcement stays at 31 lb in the original SS-4 calculation. Grate and frame weights are not reported for SS-4.

Inlet 3 · SS-3

Station: 102+00
Pipe: 18 in. round
Entered height: 3.5 ft
Listed minimum: 3.5 ft
Grate: 200.000 lb
Frame: 244.000 lb

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.5 ft)	0.869	76.000
Additional height (0.0000 ft)	0.000	0.000
Inlet quantity	0.869	76.000

Additional height uses 0.184 yd³/ft of concrete and 17 lb/ft of reinforcement. Grate and frame weights are fixed at 200 lb and 244 lb per SS-3 inlet.

Inlet 4 · SS-4

Station: 103+00
Pipe: 15 in. round
Entered height: 4.5 ft
Listed minimum: 3.125 ft
Grate: —
Frame: —

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.125 ft)	0.640	31.000
Additional height (1.3750 ft)	0.254	0.000
Inlet quantity	0.894	31.000

Additional height increases concrete by 0.185 yd³/ft only. Reinforcement stays at 31 lb in the original SS-4 calculation. Grate and frame weights are not reported for SS-4.

Inlet 5 · SS-3

Station: 104+00
Pipe: 18 in. round
Entered height: 3.5 ft
Listed minimum: 3.5 ft
Grate: 200.000 lb
Frame: 244.000 lb

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.5 ft)	0.869	76.000
Additional height (0.0000 ft)	0.000	0.000
Inlet quantity	0.869	76.000

Additional height uses 0.184 yd³/ft of concrete and 17 lb/ft of reinforcement. Grate and frame weights are fixed at 200 lb and 244 lb per SS-3 inlet.

Inlet 6 · SS-4

Station: 105+00
Pipe: 15 in. round
Entered height: 4.5 ft
Listed minimum: 3.125 ft
Grate: —
Frame: —

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.125 ft)	0.640	31.000
Additional height (1.3750 ft)	0.254	0.000
Inlet quantity	0.894	31.000

Additional height increases concrete by 0.185 yd³/ft only. Reinforcement stays at 31 lb in the original SS-4 calculation. Grate and frame weights are not reported for SS-4.

Inlet 7 · SS-3

Station: 106+00
Pipe: 18 in. round
Entered height: 3.5 ft
Listed minimum: 3.5 ft
Grate: 200.000 lb
Frame: 244.000 lb

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.5 ft)	0.869	76.000
Additional height (0.0000 ft)	0.000	0.000
Inlet quantity	0.869	76.000

Additional height uses 0.184 yd³/ft of concrete and 17 lb/ft of reinforcement. Grate and frame weights are fixed at 200 lb and 244 lb per SS-3 inlet.

Inlet 8 · SS-4

Station: 107+00
Pipe: 15 in. round
Entered height: 4.5 ft
Listed minimum: 3.125 ft
Grate: —
Frame: —

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.125 ft)	0.640	31.000
Additional height (1.3750 ft)	0.254	0.000
Inlet quantity	0.894	31.000

Additional height increases concrete by 0.185 yd³/ft only. Reinforcement stays at 31 lb in the original SS-4 calculation. Grate and frame weights are not reported for SS-4.

Inlet 9 · SS-3

Station: 108+00
Pipe: 18 in. round
Entered height: 3.5 ft
Listed minimum: 3.5 ft
Grate: 200.000 lb
Frame: 244.000 lb

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.5 ft)	0.869	76.000
Additional height (0.0000 ft)	0.000	0.000
Inlet quantity	0.869	76.000

Additional height uses 0.184 yd³/ft of concrete and 17 lb/ft of reinforcement. Grate and frame weights are fixed at 200 lb and 244 lb per SS-3 inlet.

Inlet 10 · SS-4

Station: 109+00
Pipe: 15 in. round
Entered height: 4.5 ft
Listed minimum: 3.125 ft
Grate: —
Frame: —

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.125 ft)	0.640	31.000
Additional height (1.3750 ft)	0.254	0.000
Inlet quantity	0.894	31.000

Additional height increases concrete by 0.185 yd³/ft only. Reinforcement stays at 31 lb in the original SS-4 calculation. Grate and frame weights are not reported for SS-4.

Inlet 11 · SS-3

Station: 110+00
Pipe: 18 in. round
Entered height: 3.5 ft
Listed minimum: 3.5 ft
Grate: 200.000 lb
Frame: 244.000 lb

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.5 ft)	0.869	76.000
Additional height (0.0000 ft)	0.000	0.000
Inlet quantity	0.869	76.000

Additional height uses 0.184 yd³/ft of concrete and 17 lb/ft of reinforcement. Grate and frame weights are fixed at 200 lb and 244 lb per SS-3 inlet.

Inlet 12 · SS-4

Station: 111+00
Pipe: 15 in. round
Entered height: 4.5 ft
Listed minimum: 3.125 ft
Grate: —
Frame: —

Component	Concrete (yd³)	Reinforcing steel (lb)
At listed minimum (3.125 ft)	0.640	31.000
Additional height (1.3750 ft)	0.254	0.000
Inlet quantity	0.894	31.000

Additional height increases concrete by 0.185 yd³/ft only. Reinforcement stays at 31 lb in the original SS-4 calculation. Grate and frame weights are not reported for SS-4.

Calculation basis and limits

Reconstructed from the supplied SS-3 executable, version 3.0, October 10, 2011. Original quantity tables, one-opening deductions, float32 calculation stores and height additions are retained. Heights below the listed minimum are blocked as a modern input safeguard.

This report is a quantity estimate. It does not check structural adequacy, pipe-opening conflicts or compliance with a current standard-drawing edition. Confirm applicability to the project before use.