ROADWAY DESIGN UTILITIES · SS-2A

Storm sewer inlet quantities

Project: SYNTHETIC SS-2A QA

County: Not entered

Prepared by: Not entered

Report date: 2026-11-01

Project quantity schedule

Inlet / station	Side	L (ft)	W (ft)	H (ft)	Pavement	Concrete (yd³)	Steel (lb)
1 Station not entered	L	5	4	4	No	2.614	218.745
2 Station not entered	L	10	4	4	Yes	3.504	428.745
Project total · 2 inlets						**6.118**	**647.490**

Dimensions are decimal feet. Pipe dimensions are inches. Project totals use unrounded inlet quantities.

Inlet calculation details

Inlet 1

Station: Not entered

Roadway side: Left

Length × width × height: 5 × 4 × 4 ft

Concrete pavement: No

Pipe openings: 1 × 15 in. round

Quantity	Concrete (yd³)	Steel (lb)
Pipe-opening deductions	0.038	0.000
Net inlet quantity	2.614	218.745

Inlet 2

Station: Not entered

Length × width × height: 10 × 4 × 4 ft

Pipe openings: 1 × 15 in. round

Roadway side: Left

Concrete pavement: Yes

Quantity	Concrete (yd³)	Steel (lb)
Pipe-opening deductions	0.038	0.000
Net inlet quantity	3.504	428.745

Reconstructed from the MDOT SS-2A.exe, version 6.0, October 10, 2011.